

	ISSUE FOR CONSTRUCTION	02.28.2019
3	COMMISSIONING COMMENTS	01.23.2019
2	PERMIT SET	07.25.2018
1	90% PRICING SET	06.18.2018
MARK	REVISIONS	DATE

ALL DIMENSIONS AND RELATIONSHIPS MUST BE VERIFIED BY CONTRACTOR. THE ARCHITECT IS TO BE NOTIFIED OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE CONSTRUCTION. DO NOT SCALE FROM DRAWINGS.

PROJECT #:	140145.001
FILENAME:	-
DRAWN:	WFW
CHECKED:	WFW
DATE:	07/25/18

ISSUE FOR CONSTRUCTION
02-28-2019

SECOND FLOOR
PLAN POWER 2

SYSTEMS

DRAWING

E-6



NOTES :

1. REFER TO DRAWING MPE-1 FOR IAW PLUMBING/FIRE PROTECTION & ELECTRICAL, GENERAL NOTES, ABBREVIATIONS, LEGENDS & DRAWING LIST.
2. UNLESS OTHERWISE NOTED: ALL 120 VOLT, 20A SINGLE PHASE CIRCUITS SHALL HAVE 2#12, 1#12G IN 3/4" AS A MINIMUM. ALL 120 VOLT, 20A SINGLE PHASE CIRCUITS OVER 70 FT. IN LENGTH SHALL BE 2#10, 1#10G IN 3/4".
3. UNLESS OTHERWISE NOTED: ALL 208 VOLT, 30A SINGLE PHASE CIRCUITS SHALL HAVE 2#12, 1#12G IN 3/4" AS A MINIMUM. ALL 208 VOLT, 30A SINGLE PHASE CIRCUITS OVER 110 FT. IN LENGTH SHALL BE 2#10, 1#10G IN 3/4".
4. ECD SHALL PROVIDE PERMANENT PHENOLIC LABEL ON ALL TRANSFORMERS PER NEC ARTICLE 450.14 TO IDENTIFY LOCATION OF LOCABLE FEEDER BREAKER SERVING TRANSFORMER.
5. UNLESS OTHERWISE NOTED, ALL RECEPTACLES LOCATED OUTSIDE SHALL BE HOUSED IN A WEATHERPROOF (WP) IN-USE (IU) ENCLOSURE AND HAVE GROUND FAULT CIRCUIT-INTERERRUPTER PROTECTION (GFI).

REF. CIRCUIT DIRECTORY	
ROOM / SUITE #	PANEL
SUITE 201	RP2-A
SUITE 202	RP2-A
SINGLE 203	RP2-A
DOUBLE 204	RP2-A
SUITE 205	RP2-A
SUITE 210	RP2-A
DOUBLE 208	RP2-A
SINGLE 209	RP2-A

REF. CIRCUIT DIRECTORY	
ROOM / SUITE #	PANEL
SINGLE 206	RP2-B
DOUBLE 207	RP2-B
SUITE 213	RP2-B
DOUBLE 214	RP2-B
SUITE 213	RP2-B
SINGLE 215	RP2-B
SINGLE 216	RP2-B
SINGLE 217	RP2-B
SINGLE 218	RP2-B

DRAWING NOTES :

- 1 TWO (2) 5" FLOOR SLEEVES, EACH WITH ONE (1) 4" EMPTY CONDUIT USED TO FISH WIRE BETWEEN 2ND AND 3RD LEVEL. SLEEVES / CONDUITS SHALL BE DEDICATED FOR TELEPHONE AND CABLE TV RISERS.
- 2 TELEPHONE & CATV 3/4"x4" PL WOOD BACKBOARD.
- 3 SINGLE STATION, WALL MOUNTED SMOKE DETECTOR IN GUEST UNITS. (TYPICAL FOR ALL UNITS WHERE INDICATED).
- 4 TYPICAL FIRE ALARM HORN DEVICE. (IN ALL ADA COMPLIANT SUITES, SAID DEVICE SHALL BE REPLACED WITH COMBINATION HORN/STROBE DEVICE). COORDINATE WITH ARCHITECT.
- 5 PROVIDE TWO (2) 5" FLOOR SLEEVES, EACH WITH ONE (1) 4" EMPTY CONDUIT, IN DECK ABOVE TO FISH WIRE BETWEEN 2ND AND 3RD AND 4TH LEVEL. SLEEVES / CONDUITS SHALL BE DEDICATED FOR TELEPHONE AND CABLE TV RISERS.
- 6 NOT USED.
- 7 DEDICATED 14" X 32" AREA FOR CONDUIT RISERS IN CHASE SHOWN.
- 8 CONDUIT RISER ACCESS AREA FOR THRU-PENETRATIONS IN SLAB ABOVE.
- 9 EC SHALL PROVIDE BACKBOX, CONDUIT AND PULL TAPE FOR STUB-UP WITH SOFFIT. REFER TO DETAILS SHEET FOR CONDUIT STUB-UP DETAIL. (TYP. FOR ALL ADAPTABLE OUTLETS AND JUNCTION BOXES).
- 10 PROVIDE NEMA-1, 30A/15A/5A DISCONNECT SWITCH AND CIRCUIT WITH 2#12, 120V, 3ΦC TO THE PANEL. INDICATED. TYPICAL FOR ALL HP UNITS.
- 11 FIREPLACE OUTLET BOX. COORDINATE WITH MANUFACTURER ON EXACT REQUIREMENTS FOR LOCATION, SIZE, ETC. CONTRACTOR SHALL ALSO PROVIDE ALL WIRING AS REQUIRED AND DIRECTED BY THE FIREPLACE MANUFACTURER.
- 12 RECEPTACLES TO BE INSTALLED ON THE SAME WALL. THESE RECEPTACLES ARE SHOWN STACKED FOR ILLUSTRATION ONLY AND SHALL SERVE THE FRIDGE (LOWER) AND COFFEE MAKER (UPPER) WITH THE GUEST ROOMS.
- 13 MAINTAIN NEC AND MANUFACTURER REQUIRED CLEARANCE.
- 14 FINAL LOCATION OF GENERATOR REMOTE ANNUNCIATOR PANELS SHALL BE AS DIRECTED BY THE OWNER.
- 15 FOR INDUCTION RANGE, WIRING SHALL BE 2#10, 3ΦC, PROVIDE HARD WIRE CONNECTION.