



DEMOLITION PLAN
SITE UTILITY

0' 10' 20' 40'
GRAPHIC SCALE : 1"=20'

NOTE:
FOR ANY IRRIGATION REMOVAL/PROTECTION
OR REMODEL, REFER TO IRRIGATION PLANS.

ABATEMENT OF TRANSITE IRRIGATION LINES
ARE INCLUDED IN THE SCOPE OF SERVICES
FOR THE GENERAL CONTRACTOR FOR THE
MAIN SITE IRRIGATION LINES FOR THE
EXISTING SYSTEM. REQUIREMENTS AND
SPECIFICATIONS ARE DEFERRED TO THE
ASBESTOS AND LEAD ABATEMENT
SPECIFICATIONS DATED AUGUST 24, 2020.

UTILITY DEMOLITION NOTES:

- 1 REMOVE EXISTING UTILITY LINE AND ALL APPURTENANCES.
CAP REMAINING END.
- 2 REMOVE EXISTING CATCH BASIN.
- 3 REMOVE EXISTING TRENCH DRAIN.
- 4 REMOVE EXISTING SLOT DRAIN AND CONCRETE ENCASEMENT.
- 5 REMOVE EXISTING FIELD SUBDRAIN SYSTEM. REFER TO NLMUSD
ABATEMENT SPECIFICATIONS.
- 6 REMOVE EXISTING VALVE.
- 7 REMOVE AND REPLACE EXISTING UTILITY LINE PER SHEET CS.01

UTILITY SALVAGE NOTES:

- A PROTECT IN PLACE EXISTING UTILITY LINE.
- B PROTECT IN PLACE EXISTING CATCH BASIN.
ADJUST TO GRADE WHERE NECESSARY.
- C PROTECT IN PLACE EXISTING TRENCH DRAIN.
- D PROTECT IN PLACE EXISTING VALVE. ADJUST TO GRADE AS NECESSARY.
- E PROTECT IN PLACE EXISTING UTILITY STRUCTURE.
ADJUST TO GRADE AS NECESSARY.
- F PROTECT IN PLACE EXISTING WATER PUMP AND VAULT.
ADJUST TO GRADE AS NECESSARY.

LEGEND

- | | |
|---------|--|
| --- | CENTER LINE |
| -X-X-X- | EXIST. FENCE |
| G | EXIST. GAS MAIN TO REMAIN |
| SS | EXIST. SANITARY SEWER TO REMAIN |
| SD | EXIST. STORM DRAIN TO REMAIN |
| W | EXIST. WATER MAIN TO REMAIN |
| RW | EXIST. RECLAIMED WATER TO REMAIN |
| FW | EXIST. FIRE WATER TO REMAIN |
| E | EXIST. ELECTRIC U/G CABLE TO REMAIN |
| T | EXIST. TELECOM LINE TO REMAIN |
| --- | EXISTING STORM DRAIN TO BE
REMOVED/RELOCATED |
| --- | EXISTING GAS LINE TO BE REMOVED/RELOCATED |
| --- | EXISTING SANITARY SEWER LINE TO
BE REMOVED/RELOCATED |
| --- | EXISTING DOMESTIC WATER LINE TO
BE REMOVED/RELOCATED |
| --- | EXISTING FIRE WATER LINE TO BE
REMOVED/RELOCATED |
| --- | EXISTING ELECTRICAL LINE TO BE
REMOVED/RELOCATED PER ELECTRICAL PLANS |
| --- | EXISTING TELECOM LINE TO BE
REMOVED/RELOCATED PER ELECTRICAL PLANS |
| --- | VALVE |

PROPERTY LINE
CENTER LINE
EXIST. FENCE
EXIST. GAS MAIN TO REMAIN
EXIST. SANITARY SEWER TO REMAIN
EXIST. STORM DRAIN TO REMAIN
EXIST. WATER MAIN TO REMAIN
EXIST. RECLAIMED WATER TO REMAIN
EXIST. FIRE WATER TO REMAIN
EXIST. ELECTRIC U/G CABLE TO REMAIN
EXIST. TELECOM LINE TO REMAIN
EXISTING STORM DRAIN TO BE
REMOVED/RELOCATED
EXISTING GAS LINE TO BE REMOVED/RELOCATED
EXISTING SANITARY SEWER LINE TO
BE REMOVED/RELOCATED
EXISTING DOMESTIC WATER LINE TO
BE REMOVED/RELOCATED
EXISTING FIRE WATER LINE TO BE
REMOVED/RELOCATED
EXISTING ELECTRICAL LINE TO BE
REMOVED/RELOCATED PER ELECTRICAL PLANS
EXISTING TELECOM LINE TO BE
REMOVED/RELOCATED PER ELECTRICAL PLANS
VALVE

REVISIONS

1. ADDENDUM #1 - 02/01/22

BRANDOW & JOHNSTON
STRUCTURAL-CIVIL ENGINEERS (BAJ) INC.
700 S. FLOWER ST. #1200, LOS ANGELES, CA 90017
(213) 620-1234
FAX (213) 594-4500
BAJ PROJECT # C190008



NORWALK LA MIRADA UNIFIED SCHOOL DISTRICT
LA MIRADA HIGH SCHOOL NEW FOOTBALL
STADIUM PROJECT
13520 ADELFA DRIVE, LA MIRADA, CA 90638

DSA # 03-120551

NAC
ARCHITECTURE

NAC NO. 161-19015
DATE 02-01-2022

DSA SUBMISSION

DEMOLITION
PLAN - SITE
UTILITY

C3.04