JOIN LINE - SEE SHEET C4.03 (WEST)

JOIN LINE - SEE SHEET C4.03 (EAST)

JOIN LINE - SEE SHEET C4.02

FF=219.80

25 RAISERS 7" EA ADJUST BOTTOM RISER TO ACCOMMODATE SLOPE

REHABILITATION OF RAMP AND RETAINING WALL PER A# 03-120869 WHICH IS APPROVED ON 11/25/20.

SEE ENLARGED GRADING PLAN-AREA B ON SHEET C4.02

SEE ENLARGED GRADING PLAN-AREA B ON SHEET C4.02

PAVEMENT LEGEND

- NEW LANDSCAPING
- NEW CONCRETE
- NEW ASPHALT CONCRETE
- NEW ARTIFICIAL TURF (OUTSIDE THE FIELD)
- NEW CRUSHED BRICK PAVEMENT

LEGEND

- PROPERTY LINE
- LOT LINE
- CENTER LINE
- NEW FENCE
- EXIST. FENCE
- ADA PATH OF TRAVEL
- FLOWLINE
- RIDGE LINE
- PROP. CONTOUR (1' INTERVAL)
- EXIST. CONTOUR (1' INTERVAL)
- PROPOSED SPOT ELEVATION
- EXISTING SPOT ELEVATION
- NEW WALL
- EXISTING WALL
- GRADE BREAK

NORTH

PRECISE GRADING PLAN

0' 10' 20' 40'

GRAPHIC SCALE : 1"=20'

NOTE TO CONTRACTOR:

CONTRACTOR TO REFER TO BLEACHER PLANS FOR BLEACHER FOUNDATION PIERS LOCATION.

CONSTRUCTION NOTES:

1. NEW BUILDING PER ARCHITECTURAL PLANS.
2. INSTALL NEW ATHLETIC TRACKS PER TRACK AND FIELD PLANS.
3. CONSTRUCT PEDESTRIAN CONCRETE PAVEMENT PER DETAIL 2 ON SHEET C2.01.
4. CONSTRUCT ASPHALT PAVEMENT PER DETAIL 1 ON SHEET C2.01.
5. SAWCUT AND JOIN FLUSH EXISTING CONCRETE PAVEMENT PER DETAIL 4 ON SHEET C2.01.
6. CONSTRUCT CONCRETE TO ASPHALT PAVEMENT TRANSITION PER DETAIL 15 ON SHEET C2.01.
7. JOIN FLUSH EXISTING ASPHALT PER DETAIL 9 ON SHEET C2.01.
8. CONSTRUCT CONCRETE TO PLANTER TRANSITION PER DETAIL 10 ON SHEET C2.01.
9. EXISTING DRAINAGE DEVICE TO REMAIN.
10. INSTALL NEW DRAINAGE DEVICE PER SHEET C5.01.
11. INSTALL NEW ARTIFICIAL TURF FIELD PER TRACK AND FIELD PLANS.
12. ADJUST UTILITY BOXES, METERS, VALVES, OR CATCH BASINS TO GRADE. FOR NON-CIVIL UTILITIES SEE THE RESPECTIVE DISCIPLINES FOR MORE DETAILS.
13. CONCRETE – SEE ARCHITECTURAL PLANS FOR FINISH.
14. CONSTRUCT CONCRETE STAIR PER SPPWC STD. PLAN 640-4.
15. CONSTRUCT NEW CHAIN LINK FENCE AND GATES PER TRACK AND FIELD PLANS AND DETAILS.
16. CONSTRUCT TRAFFIC RATED CONCRETE PAVEMENT PER DETAIL 5 ON SHEET C2.01.
17. CONSTRUCT CURB PER DETAIL 7 ON SHEET C2.01.
18. CONSTRUCT CURB PER DETAIL 16 ON SHEET C2.01.
19. CONSTRUCT CMU RETAINING WALL PER DETAIL 4 ON SHEET C2.02.
20. CONSTRUCT CONCRETE RETAINING WALL PER DETAIL 6 ON SHEET C2.02.
21. INSTALL FIELD POLES PER ARCHITECTURAL PLANS AND DETAILS.
22. CONSTRUCT CURB TRANSITION PER DETAIL 6 ON SHEET C2.01.
23. CONSTRUCT CURB TRANSITION BY RAISING THE PAVEMENT TO TOP OF CURB AS SHOWN ON PLAN
24. CONSTRUCT EXTENDED THICKEN EDGE PER DETAIL 17 ON SHEET C2.01.
25. INSTALL NEW ARTIFICIAL TURF PER TRACK AND FIELD PLANS.
26. INSTALL NEW CRUSHED BRICK PAVEMENT PER TRACK AND FIELD PLANS.
27. INSTALL NEW REDWOOD HEADER PER DETAIL 18 ON SHEET C2.01.
28. IRRIGATION PUMP PER TRACK AND FIELD PLANS AND DETAILS.
29. GATE PER TRACK AND FIELD PLANS AND DETAILS.
30. CONSTRUCT RAMP/STAIR LANDING PER BLEACHER DRAWINGS.
31. CONSTRUCT CONCRETE PAD PER TRACK AND FIELD PLANS.
32. INSTALL SCOREBOARD PER ARCHITECTURAL PLANS.
33. CONSTRUCT CONCRETE PAD PER MECHANICAL PLANS.



KEY MAP
GRAPHIC SCALE : 1"=500'
NORTH

© 2015 NAC Inc.

IDENTIFICATION STAMP
DIV. OF THE STATE ARCHITECT
APP: 03-120551 INC:
REVIEWED FOR
SS ☑ FLS ☑ ACS ☑
DATE: 01/11/2021

REVISIONS

BRANDOW & JOHNSTON
STRUCTURAL-CIVIL ENGINEERS (BRJ HBK, INC.)
700 S FLOWER ST #1800, LOS ANGELES, CA 90017
T: (213) 596-4500
WWW.BJSCE.COM
BRJ PROJECT # C19-0038
EST. 1945

REGISTERED PROFESSIONAL ENGINEER
EDWARD S. WU
No. C80534
State of California

LICENSED ARCHITECT
HELENA L. JUBANY
No. C22214
Ren. 8-31-20
STATE OF CALIFORNIA

NORWALK LA MIRADA UNIFIED SCHOOL DISTRICT
LA MIRADA HIGH SCHOOL NEW FOOTBALL STADIUM PROJECT
13520 ADELFA DRIVE, LA MIRADA, CA. 90638

DSA # 03-120551

NAC ARCHITECTURE
NAC NO. 161-19015
DATE 8-26-2020

DSA SUBMISSION

PRECISE GRADING PLAN

C4.01

H:\C19-0037 - NAC - NLMUSD La Mirada HS\Engineering\Drawings\C4.01 gr.dwg Plotted On Dec 15, 2020-9:44am by bnguyen